



NOTES:

1. Specifications reference the Standard Specifications for Public Work Construction "Green Book" Latest Edition
2. Existing asphalt shall be saw-cut or cold milled in a straight, clean manner without chipping or breaking the adjacent pavement. All edges shall be clean and vertical. All cuts shall be parallel or perpendicular to the street centerline with 90 degree corners whenever practical.
3. Upon removal of existing asphalt concrete, slot patch area shall be filled in flush to finish grade with temporary asphalt concrete to maintain pedestrian crossing areas, at pedestrians ramps or to maintain vehicular traffic until the final asphalt concrete restoration is completed.
4. Asphalt concrete restoration shall be placed within of 7-days after placement of curbs and gutters. Asphalt concrete restoration shall match the existing structural section of asphalt concrete and shall be a minimum of 3-inches thick on residential streets or 6-inches thick non-residential streets whichever is greater. Asphalt concrete pavement shall be placed in accordance to Section 306-13 without the additional 1-inch of asphalt concrete as specified. After completion of asphalt concrete paving, the perimeter of the trench shall be seam sealed.
5. Asphalt concrete shall be placed in two lifts with no lift permitted greater than 4-inches thick.
6. Asphalt concrete materials shall conform to the following:
Asphalt Concrete: Grade and Class: PG 64-10, C2 (Section 203-6.4.4) or C2 (Section 203-6.5.4)
7. Additional placement of slurry seal or chip seals shall be applied as required by the City for recently resurfaced streets or those streets within a trench cut moratorium area. Asphalt restorations which do not meet these requirements are subject to removal and replacement.

REVISION	APPROVED	DATE	CITY OF SANTEE STANDARD DRAWING	APPROVED:
ORIGINAL	C. SCHMITZ	3/20/2018		SLOT TRENCH RESURFACING
RUBBERIZED ASPHALT	S. MILLER	8/30/2018	CITY ENGINEER	
ASPHALT CONCRETE	S. MILLER	6/6/2022	R.C.E. 60112 DATE: 6/8/2023	
				DRAWING NUMBER PW - 03